

LGD410Y Mining Bulldozer

| ENGINE | |
|-----------------------|---|
| Model | Cummins KTA19-C525 |
| Туре | Turbocharged vertical four-stroke, PT pump injection |
| Flywheel power | 306Kw |
| Rated speed (r/min) | 2000rpm |
| Number | 6-Ф159×159mm |
| cylinders-bore×stroke | |
| Starting method | Electric starting 9kW/24V |
| Battery | 24VOptimax |
| Air cleaner | Dry horizontal type with pre-cleaner |
| TRANSMISSION SYSTEM | |
| Torque converter | 3-element, single-stage, single phase |
| Transmission | Hand-operated, Hydraulic shift, Planetary gear, multiple-disc clutch, hydraulic |
| | actuated, forced lubrication by gear pump, 3 forward speeds and 3 reverse |
| | speeds. |
| Bevel gear | Helical bevel gear, Splash lubricated |

Shanghai Longji Construction Machinery Co., Ltd.

Add: Room 1311, Building C, Lane 58, No.1 East Xinjian Road, Minhang District, Shanghai

City, China

Post Code: 201100 E-mail: mailto:info@shlongji.com

Tel: +86-21-541-71571 Fax: +86-21-541-71572

| Steering clutch | Wet, Multiple disc, Spring loaded, Hand-operated with booster and | |
|-----------------------------------|--|--|
| | hydraulic-released | |
| | Wet, band brake, operated with hydraulic booster | |
| Final drive | Spur gear, planetary gear driving, one reduction, splash lubrication | |
| UNDER CARRIAGE | | |
| Sprocket | Segmented | |
| Number of track shoes (each side) | (4 single, 3 double) | |
| , | Hydraulic adjusted | |
| | all track rollers, carrier rollers, sprocket and front idlers | |
| TRAVEL SPEED (km/h) | | |
| Forward 1 | 3.4km/h | |
| Forward 2 | 6.7km/h | |
| Forward 3 | 12.2km/h | |
| | 4.2km/h | |
| Reverse 2 | 8.0km/h | |
| | | |
| Reverse 3 | 14.8km/h | |
| TRACK | | |
| Type | Lubricated track | |
| Track pitch | 260.35mm | |
| Track width | 610mm | |
| Number of track shoes (each side) | 40 | |
| Length of track on ground | 3425mm | |
| Ground clearance | 600mm | |
| Ground pressure | ≤0.109Mpa | |
| Track gauge | 2260mm | |
| HYDRAULIC CONTROL S | SYSTEM | |
| Working pressure | 20Mpa | |
| Rated delivery | 264L/Min | |
| Pump | CBZb4160T gear pump | |
| Control valve | Hydraulic-operated plunger, loaded feedback, servo controlling | |
| Valve position | Raise, Hold, Lower, Float | |
| Cylinder, Bore × Rod | | |
| ×Stroke | Ф140×Ф90×1440mm | |
| WORK EQUIPMENT | | |
| Blade type | Semi-U blade | |
| Width ×Height | 4314×1841mm | |
| Max. lift above ground | 1620mm | |
| | | |

Shanghai Longji Construction Machinery Co., Ltd. Add: Room 1311, Building C, Lane 58, No.1 East Xinjian Road, Minhang District, Shanghai

City, China

E-mail: mailto:info@shlongji.com **Post Code: 201100**

Fax: +86-21-541-71572 Tel: +86-21-541-71571

| Max. drop below ground | 749mm |
|------------------------|------------------|
| Pitch adjustment | 52° |
| Grade ability | 30° |
| Max .tilt | 1000mm |
| Length × Width ×Height | 7100×4314×3900mm |
| Weight | 45362kg |

Shanghai Longji Construction Machinery Co., Ltd. Add: Room 1311, Building C, Lane 58, No.1 East Xinjian Road, Minhang District, Shanghai

City, China

Post Code: 201100 E-mail: mailto:info@shlongji.com

Tel: +86-21-541-71571 Fax: +86-21-541-71572